BRUHAT BANGALORE MAHANAGARA PALIKE, YALAHANKA ZONE

Executive Engineer,Byatarayanapura Division, B.B.M.P., Bangalore - 92

Tender Notification No. **Sl. No.:** 75.

BBMP | EE | Btp | Ten | 02 | 12-13, dated : 15-05-2012.

DRAFT TENDER SCHEDULE-B

Name of Work :- Estimate for the work of Improvements of roads and Construction of RCC drain in 'A' block, Sahakaranagar in Ward No. 7 Est.Cost Rs: 1900000.00 Job Code No: 007-12-000057

Sl. No	Approved Quantity as per Estimate	Discriptions of Items	Unit	Sanctioned Rates as per Estimate	Rates Quoted	
				Rs.	Figures	In Words
1	228.60 ✓	Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods Complete as per Specification and Directions of Engineer in charge of the Work	Cum	62.86 ✓		
2	302.40 ✓	Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and slectrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m. In depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking specification. Complete as per Specification and Directions of Engineer in charge of the Work	Cum	217.08 ✓		
3	37.80 ✓	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms. thick well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per Specification and Directions of Engineer in charge of the Work	Cum	3939.41 ✓		

4	59.85	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses. parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc..,including cost of all materials, labour, HOM of machinery, curing,Complete as per Specification and Directions of Engineer in charge of the Work	Cum	5296.75		
5	47.88	Providing T.M.T steel reinforcement for R.C.C work including straightening cutting, bending, hooking, placing wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of ,materials, labor HOM of machinery Complete as per Specification and Directions of Engineer in charge of the Work	**Qtl**	**7347.82**		
6	252.00	Providing and laying 10cms thick precast R.C.C. slabs (DATA RATE) Complete as per Specification and Directions of Engineer in charge of the Work	**Sqm**	**1500.00**		
7	1008.00	Providing and removing centering, shuttering, shuttering, strutting, propping etc.., and removal of form work for vertical surface such as walls at any thickness, including attached plasters, buttresses, plinth and string courses cost of all materials, labour Complete as per Specification and Directions of Engineer in charge of the Work	**Sqm**	**221.40**		

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ .....( )
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಆಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ

Signature of the Contractor
Reg. No.
Postal Address

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92